

NRC7292 Standalone SDK Release Note

(v1.4)

Ultra-low power & Long-range Wi-Fi

Ver 1.0 Mar. 30, 2023

NEWRACOM, Inc.

NRC7292 Standalone SDK Release Note (v1.4) Ultra-low power & Long-range Wi-Fi

© 2023 NEWRACOM, Inc.

All right reserved. No part of this document may be reproduced in any form without written permission from Newracom.

Newracom reserves the right to change in its products or product specification to improve function or design at any time without notice.

Office

Newracom, Inc. 505 Technology Drive, Irvine, CA 92618 USA http://www.newracom.com

Contents

1		Overview	6
2		Contents of software release package	6
3		Standalone SDK Package	8
	3.1	General guide	8
		Supported 3 rd party libraries	
4		SW Release Package	9
		Features	
	4.2	Resolved issues	10
	4.3	Changed items	12
	4 4	Known issues	14

List of Tables

Table 2.1	Contents of NRC7292 standalone SDK package	7
	Resolved issues	
Table 4.2	Changed items	12
Table 4.3	Known issues	14

List of Figures

Figure 2.1	NRC7292 standalone SDK package directory

1 Overview

The IEEE 802.11ah is a new Wi-Fi standard created to fulfill the requirements of a variety of IoT applications. Newracom's NRC7292 chip provides two modes of operation: host mode and standalone mode. Host mode necessitates an external host device, like the Raspberry Pi3 included in Newracom's EVK, to supply 11ah Wi-Fi connectivity. On the other hand, standalone mode enables users to develop their own applications using the APIs provided in the standalone package, compile binaries with the SDK, and execute them on the NRC7292. In standalone mode, users can use the NRC7292's various peripheral interfaces to collect sensor data and transmit it to the server over the 11ah network. Furthermore, the NRC7292 offers an AT commands application in standalone mode, allowing users to utilize the 11ah Wi-Fi network.

This document outlines the NRC7292 software package for standalone mode.

2 Contents of software release package

The software release package encompasses all the necessary components for utilizing the most recent features, including firmware libraries, header files, APIs, sample codes, downloader tool, makefile, and documentation. Figure 2.1 illustrates the directory structure of the package, while Table 2.1 presents a summary of its contents.




Figure 2.1 NRC7292 standalone SDK package directory

Table 2.1 Contents of NRC7292 standalone SDK package

Directory	Description
doc	Documents for standalone guide document and SDK API lists
lib	NRC7292 modem library and 3 rd party libraries.
make	makefiles and configuration files
sdk/inc	SDK API header files and SDK common header files.
sdk/apps	Several kinds of reference sample applications.
atcmd	ATCMD binaries and reference codes for the host platform
bdf	A Board Data File (BDF) contains power tables based on a country, channel, target hardware version, MCS (Modulation Coding Scheme).
tools/AT_CMD_Test_Tool	AT command test tool for UART interface
tools/external_tools	The FirmwareFlashTool is a firmware uploader.

The information of the library released in this package is as follows.

Library (including 3rd party)

Name : libmodem.aLocation : lib/modem

o Version : 1.4

o Build date : Mar. 30, 2023

3 Standalone SDK Package

3.1 General guide

To gain a broad understanding of the software package, developers can refer to the 'UG-7292-004-Standalone SDK.pdf' document. This resource offers instructions on configuring the software build environment, compiling standalone binaries, and downloading binary and sample applications. Furthermore, developers can utilize the 'UG-7292-005-Standalone SDK API.docx' document, which provides a list of supported APIs that can be used in conjunction with the NRC7292. These APIs enable users to implement services connected to Wi-Fi connections and peripherals. For additional assistance, the 'UG-7292-006-AT_Command.pdf' document offers a guide to AT commands.

3.2 Supported 3rd party libraries

The standalone SDK package for the NRC7292 contains numerous third-party libraries, which are detailed in the 'UG-7292-005-Standalone SDK API.docx' document along with their corresponding URLs. FreeRTOS, LwIP, and Mbed TLS are among these libraries, and they are essential for the standalone SDK to function properly.

- FreeRTOS
- LwIP
- Mbed TLS
- MQTT
- cJSON
- Mini-XML
- AWS (Amazon web service)
- NVS (Non-volatile storage)
- Device libraries
 - BME680 (Gas, humidity, pressure, and temperature sensor)
 - SSD1306 (OLED/PLED controller)
 - SGP30 (Air quality sensor)
 - o SHT30 (Temperature and humidity sensor)

4 SW Release Package

4.1 Features

The NRC7292 software release package contains the following features.

• Build Environment

Update Linux based build environment (v1.3.0)

• AT-CMD

- o FOTA command (v1.3.2)
- o Power save (v1.3.4)
- WPA3-SAE/OWE (v1.3.4)
- o Passive receiving mode (v1.4)

• Firmware Refactoring with following updates (v1.4)

- o SDK API updates
- o AT-CMD updates

	Command	Event
Remove	AT+WROAM	+WEVENT:"CONNECT_FAIL"
	AT+SRXLOGLEVEL	
Update	AT+WTXPOWER	
	AT+WCONN	
	AT+WDHCP	
	AT+WTIMEOUT	
	AT+SOPEN	
	AT+SSEND	
Add	AT+WDNS	+WEVENT:"DHCP_START"
	AT+SRECV	+WEVENT:"DHCP_STOP"
	AT+SRECVMODE	+WEVENT:"DHCP_BUSY"
	AT+SRECVINFO	+WEVENT:"DHCP_FAIL"
	AT+SADDRINFO	+WEVENT:"DHCP_SUCCESS"
	AT+STCPNODELAY	+WEVENT:"DHCP_TIMEOUT"
		+WEVENT:"STA_CONNECT"
		+WEVENT:"STA_DISCONNECT"
		+SEVENT:"RECV_READY"

- Duty cycle support
- o Power save enhancement: deep sleep optimization

- o Remove modem sleep support
- o Support for multiple regulatory domains with a single firmware
- o Regulatory domain updates: KR MIC, JP
- o ARM GNU toolchain upgrade to version 10.3-2021.10
- o Sample application updates

4.2 Resolved issues

The table is the resolve issues since v1.3.1.

Table 4.1 Resolved issues

Version	Description
v1.3.1	Sending block in softap tcp server
	Sending block during multiple tcp receiving and sending operations in non-blocking socket
	Fix AT+ATZ operation
	Fix the system assert when the unsupported channel is assigned in softap
v1.3.2	Fix ToS(IP Header) to TID/AC mapping issue
	Fixed to reflect beacon rssi value in scan results
	Fixed Background scan issue in standalone STA
	Fix an issue where UART settings are not changed with the AT+UART set command.
	Improvement downlink throughput in 4MHz
	Fix Association Timeout Issue : Set Fragment Number to be 0
v1.3.4	Improvement reconnection time after deep sleep
	Fix a hang issue during modem sleep
	Fix abnormal addba/delba operation for AMPDU
	Fix an issue that the scan is repeated without reassociation
	Fix an issue that DHCP client is blocked
v1.3.4	Fix wakeup issues in modem sleep
rev01	Fix scan results flags for WPA3 in atcmd

v1.3.4	Fix iperf bug in raspi-atcmd-clli (v1.2.2)
rev02	Fix channel setting issue. Add new country code for ATCMD
v1.3.4	N/A
rev03	
v1.3.4	Added US full channels (45 Channels) for 11AH: 'a' channels and some 'g' channels
rev04	Added return value when buffer allocation is failed
	Fixed ATCMD FOTA download issue
	Fixed ATCMD ROAMING connection issue
	Fixed Roaming and Scan issues
	Fixed NDP Probe Request after deep sleep
	Added to set BI/SBI during connection on STA
	Fixed not enter modem sleep
v1.3.4	Fixed DHCP server's MTU size for fixing unintended MPDU size after association
rev05	Fixed scan operation with channel lists
v1.3.4	Exception handling of IP length mismatch
rev06	
v1.3.4	N/A
rev07	
v1.3.4	Fix TX power setting for response control frame
rev08	
v1.3.4	Improve the spurious emission performance in JP channels
rev09	
v1.4	Firmware refactoring

4.3 Changed items

The table is the changed items since v1.3.1.

Table 4.2 Changed items

Version	Description Description
v1.3.1	Support KR MIC band (925.5-930.5) in host_kr_mic package
V1.5.1	standalone kr mic package supports 925.5 – 930.5 Mhz for KR.
	Enhancement ATCMD with uart
	Increase the supported max baudrate (115200) using DMA
	Added i2c sensor read operation in sample_ps_tcp_client
	Added Non-tim mode deep sleep in sample_ps_standalone & sample_ps_tcp_client
	Assign interval for deep sleep duration
	Change temperature compensation value
	Temperature power offset is now linearly interpolated, etc.
v1.3.2	RX gain table, RSSI offset, LNA Swithcing point, 2Mhz mode threshold value
	Restructuring sf_sys_config_t data structure in FLASH
	Rename for add_network function and added remove_network in wifi api
	Added 'AT+WFOTA' and 'AT+WROAM'
v1.3.4	Support APIs for WPA3 SAE/OWE
	Added WPS-PBC in sample_wps_pbc
	Enhancement of stability with WDT Reset
	Support BSS Max Idle
	Support CSA (Channel Switch Announcement)
	Add new events for FOTA operation
	Add AT+WSTAINFO, AT+WSLEEP and removed AT+SLEEP, AT+WMCS
v1.3.4	Add ATCMD sources in a package
rev01	Disable the default CONFIG_WPS feature in FreeRTOS.config
v1.3.4	Add build configuration info in ATCMD logs
rev02	

v1.3.4	Change ATCMD task priority from 0 to 2
rev03	
v1.3.4	Update FOTA operation using json file
rev04	Enable NDP Probe Request by default
	Update Wi-Fi events (v1.22.4)
	Added time & wakeup api
	Added NVS to start default if CONFIG_NVS_FLASH is defined
	Sample for Power save (Non-Tim mode)
	Added API for Carrier sensing(CS) time and Pause time
	Update console print function to enable/disable print from user app
v1.3.4	Added APIs (ATCMD & SDK API)
rev05	: duty cycle, CCA threshold, set mcs, bss max idle
v1.3.4	Updated APIs and related samples
rev06	: spi, uart, i2c
	Added standalone board data
	Added set/get scan frequency list
	Updated an ATCMD host application
v1.3.4	Update reverse_scrambler configuration to interoperate with HaLow certified device
rev07	To be interoperable with nrc7292_sw_pkg v1.3.4 rev04
v1.3.4	Update AU/NZ channels according to IEEE 802.11-2020
rev08	Update JP channels
v1.3.4	Enable the 1MHz TX filter for JP channel
rev09	Enable traveling pilot
v1.4	Firmware refactoring

4.4 Known issues

Table 4.3 presents all know issues in the version 1.4.

Table 4.3 Known issues

Category	Description
Security	The initial connection time for WPA3-SAE/OWE can be quite lengthy (> 15 seconds) due to the substantial computational load required by software for large number operations.
SoftAP	The SoftAP disable/enable sequence on the standalone mode is not supported.